



PCT/GB 2004 / 0 0 2 6 4 2



INVESTOR IN PEOPLE

The Patent Office
Concept House
Cardiff Road
Newport

South Wales
NP10 8QQ
3 JUL 2004

WIPO

PCT

I, the undersigned, being an officer duly authorised in accordance with Section 74(1) and (4) of the Deregulation and Contracting Out Act 1994, to sign and issue certificates on behalf of the Comptroller-General hereby certify that annexed hereto is a true copy of the international application filed on 18 June 2003 under the Patent Cooperation Treaty at the UK Receiving Office. The application was allocated the number PCT/GB2003/002621.

In accordance with the Patents (Companies Re-registration) Rules 1982, if a company named in this certificate and any accompanying documents has re-registered under the Companies Act 1980 with the same name as that with which it was registered immediately before re-registration save for the substitution as, or the inclusion as, the last part of the name of the words "public limited company" or their equivalents in Welsh, references to the name of the company in this certificate and any accompanying documents shall be treated as references to the name with which it is so re-registered.

In accordance with the rules, the words "public limited company" may be replaced by p.l.c., plc, P.L.C. or PLC.

Re-registration under the Companies Act does not constitute a new legal entity but merely subjects the company to certain additional company law rules.

Signed

Dated

05 JULY 2004

**PRIORITY
DOCUMENT**
SUBMITTED OR TRANSMITTED IN
COMPLIANCE WITH RULE 17.1(a) OR (b)

BEST AVAILABLE COPY

An Executive Agency of the Department of Trade and Industry

PCT REQUEST

1/6

Original (for SUBMISSION) - printed on 18.06.2003 11:19:31 AM

FP-09-0638

0	For receiving Office use only	
0-1	International Application No.	PCT/GB 2003 / 0 0 2 6 2 . 1
0-2	International Filing Date	18 JUNE 2003 / 18-06-03
0-3	Name of receiving Office and "PCT International Application"	United Kingdom Patent Office PCT International Application
0-4	Form - PCT/RO/101 PCT Request	
0-4-1	Prepared using	PCT-EASY Version 2.92 (updated 01.04.2003)
0-5	Petition	
	The undersigned requests that the present international application be processed according to the Patent Cooperation Treaty	
0-6	Receiving Office (specified by the applicant)	United Kingdom Patent Office (RO/GB)
0-7	Applicant's or agent's file reference	FP-09-0638
I	Title of invention	FLOW FIELD PLATE GEOMETRIES
II	Applicant	
II-1	This person is:	applicant only
II-2	Applicant for	all designated States except US
II-4	Name	THE MORGAN CRUCIBLE COMPANY PLC
II-5	Address:	Morgan House Madeira Walk Windsor, Berkshire SL4 1EP United Kingdom
II-6	State of nationality	GB
II-7	State of residence	GB
III-1	Applicant and/or inventor	
III-1-1	This person is:	applicant and inventor
III-1-2	Applicant for	US only
III-1-4	Name (LAST, First)	TURPIN, Mark, Christopher
III-1-5	Address:	(2/0) The Morgan Crucible Company plc Morgan House Madeira Walk Windsor, Berkshire SL4 1EP United Kingdom
III-1-6	State of nationality	GB
III-1-7	State of residence	GB

Ro/GB.

PCT REQUEST

FP-09-0638

Original (for SUBMISSION) - printed on 18.06.2003 11:19:31 AM

III-2	Applicant and/or inventor	
III-2-1	This person is:	applicant and inventor
III-2-2	Applicant for	US only
III-2-4	Name (LAST, First)	CHAPMAN, Alan, Robert
III-2-5	Address:	Morgan Group Technology Bewdley Road Stourport on Severn, Worcestershire DY13 8QR United Kingdom
III-2-6	State of nationality	GB
III-2-7	State of residence	GB
IV-1	Agent or common representative; or address for correspondence	agent
	The person identified below is hereby/has been appointed to act on behalf of the applicant(s) before the competent International Authorities as:	
IV-1-1	Name	Phillips & Leigh
IV-1-2	Address:	5 Pemberton Row London, Greater London EC4A 3BA United Kingdom
IV-1-3	Telephone No.	+44 20 7822 8888
IV-1-4	Facsimile No.	+44 20 7822 8899
IV-1-5	e-mail	mail@pandl.com
V	Designation of States	
V-1	Regional Patent (other kinds of protection or treatment, if any, are specified between parentheses after the designation(s) concerned)	AP: GH GM KE LS MW MZ SD SL SZ TZ UG ZM ZW and any other State which is a Contracting State of the Harare Protocol and of the PCT EA: AM AZ BY KG KZ MD RU TJ TM and any other State which is a Contracting State of the Eurasian Patent Convention and of the PCT EP: AT BE BG CH&LI CY CZ DE DK EE ES FI FR GB GR HU IE IT LU MC NL PT RO SE SI SK TR and any other State which is a Contracting State of the European Patent Convention and of the PCT OA: BF BJ CF CG CI CM GA GN GQ GW ML MR NE SN TD TG and any other State which is a member State of OAPI and a Contracting State of the PCT

AA Ro/GB.

PCT REQUEST

FP-09-0638

Original (for SUBMISSION) - printed on 18.06.2003 11:19:31 AM

V-2	National Patent (other kinds of protection or treatment, if any, are specified between parentheses after the designation(s) concerned)	AE AG AL AM AT AU AZ BA BB BG BR BY BZ CA CH&LI CN CO CR CU CZ DE DK DM DZ EC EE ES FI GB GD GE GH GM HR HU ID IL IN IS JP KE KG KP KR KZ LC LK LR LS LT LU LV MA MD MG MK MN MW MX MZ NI NO NZ OM PG PH PL PT RO RU SC SD SE SG SK SL TJ TM TN TR TT TZ UA UG US UZ VC VN YU ZA ZM ZW	
V-5	Precautionary Designation Statement In addition to the designations made under items V-1, V-2 and V-3, the applicant also makes under Rule 4.9(b) all designations which would be permitted under the PCT except any designation(s) of the State(s) indicated under item V-6 below. The applicant declares that those additional designations are subject to confirmation and that any designation which is not confirmed before the expiration of 15 months from the priority date is to be regarded as withdrawn by the applicant at the expiration of that time limit.		
V-6	Exclusion(s) from precautionary designations	NONE	
VI-1	Priority claim of earlier national application		
VI-1-1	Filing date	24 June 2002 (24.06.2002)	
VI-1-2	Number	0214522.5	
VI-1-3	Country	GB	
VI-2	Priority document request The receiving Office is requested to prepare and transmit to the International Bureau a certified copy of the earlier application(s) identified above as item(s):	VI-1	
VII-1	International Searching Authority Chosen	European Patent Office (EPO) (ISA/EP)	
VIII	Declarations	Number of declarations	
VIII-1	Declaration as to the identity of the inventor	1	
VIII-2	Declaration as to the applicant's entitlement, as at the international filing date, to apply for and be granted a patent	1	
VIII-3	Declaration as to the applicant's entitlement, as at the international filing date, to claim the priority of the earlier application	-	
VIII-4	Declaration of inventorship (only for the purposes of the designation of the United States of America)	-	
VIII-5	Declaration as to non-prejudicial disclosures or exceptions to lack of novelty	-	

PCT REQUEST

5/6

Original (for SUBMISSION) - printed on 18.06.2003 11:19:31 AM

FP-09-0638

VIII-2-1	Declaration: Entitlement to apply for and be granted a patent Declaration as to the applicant's entitlement, as at the international filing date, to apply for and be granted a patent (Rules 4.17(ii) and 51bis.1(a)(ii)), in a case where the declaration under Rule 4.17(iv) is not appropriate: Name:	in relation to this international application THE MORGAN CRUCIBLE COMPANY PLC is entitled to apply for and be granted a patent by virtue of the following:
VIII-2-1 (iv)		an assignment from TURPIN, Mark, Christopher to THE MORGAN CRUCIBLE COMPANY PLC, dated 24 June 2003 (24.06.2003)
VIII-2-1 (ix)	This declaration is made for the purposes of:	all designations except the designation of the United States of America

PCT REQUEST

FP-09-0638


Original (for SUBMISSION) - printed on 18.06.2003 11:19:31 AM

VIII-1-1	Declaration: Identity of the Inventor Declaration as to the identity of the inventor (Rules 4.17(i) and 51bis.1(a)(i))	in relation to this international application
...	Name: Address:	TURPIN, MARK CHRISTOPHER of c/o The Morgan Crucible Company plc Morgan House Madeira Walk Windsor Windsor, Berkshire SL4 1EP United Kingdom is the inventor of the subject matter for which protection is sought by way of this international application
	Name: Address:	CHAPMAN, Alan, Robert of c/o Morgan Group Technology Limited Bewdley Road Stourport on Severn, Worcestershire DY13 8QR United Kingdom is the inventor of the subject matter for which protection is sought by way of this international application
	This declaration is made for the purposes of:	all designations except the designation of the United States of America

PCT REQUEST

FP-09-0638

Original (for SUBMISSION) - printed on 18.06.2003 11:19:31 AM

IX	Check list	number of sheets	electronic file(s) attached
IX-1	Request (including declaration sheets)	6	-
IX-2	Description	11	-
IX-3	Claims	2	-
IX-4	Abstract	1	EZABST00.TXT
IX-5	Drawings	7	-
IX-7	TOTAL	27	-
	Accompanying items	paper document(s) attached	electronic file(s) attached
IX-8	Fee calculation sheet	✓	-
IX-10	Original general power of attorney	✓	-
IX-11	Copy of general power of attorney	reference no. Morgan	-
IX-11	Copy of general power of attorney	reference no. Turpin	-
IX-17	PCT-EASY diskette	-	Diskette
IX-19	Figure of the drawings which should accompany the abstract	1	
IX-20	Language of filing of the international application	English	
X-1	Signature of applicant, agent or common representative		
X-1-1	Name	Phillips & Leigh	
X-1-2	Name of signatory	J.C. Boff	
X-1-3	Capacity	Partner	

FOR RECEIVING OFFICE USE ONLY

10-1	Date of actual receipt of the purported international application	18 JUNE 2003	18-06-03
10-2	Drawings:		
10-2-1	Received	✓	
10-2-2	Not received		
10-3	Corrected date of actual receipt due to later but timely received papers or drawings completing the purported international application		
10-4	Date of timely receipt of the required corrections under PCT Article 11(2)		
10-5	International Searching Authority	ISA/EP	
10-6	Transmittal of search copy delayed until search fee is paid		

FOR INTERNATIONAL BUREAU USE ONLY

11-1	Date of receipt of the record copy by the International Bureau	
------	--	--

FLOW FIELD PLATE GEOMETRIES

This invention relates to fuel cells and electrolyzers, and is particularly, although not exclusively, applicable to proton exchange membrane fuel cells and electrolyzers.

- 5 Fuel cells are devices in which a fuel and an oxidant combine in a controlled manner to produce electricity directly. By directly producing electricity without intermediate combustion and generation steps, the electrical efficiency of a fuel cell is higher than using the fuel in a traditional generator. This much is widely known. A fuel cell sounds simple and desirable but many man-years of work have been expended in recent years attempting to produce practical
- 10 fuel cell systems. An electrolyzer is effectively a fuel cell in reverse, in which electricity is used to split water into hydrogen and oxygen.

- Both fuel cells and electrolyzers are likely to become important parts of the so-called "hydrogen economy". In the following, reference is made to fuel cells, but it should be remembered that the same principles apply to electrolyzers. One type of fuel cell in commercial production is the
- 15 so-called proton exchange membrane (PEM) fuel cell [sometimes called polymer electrolyte or solid polymer fuel cells (PEFCs)]. Such cells use hydrogen as a fuel and comprise an electrically insulating (but ionically conducting) polymer membrane having porous electrodes disposed on both faces. The membrane is typically a fluorosulphonate polymer and the electrodes typically comprise a noble metal catalyst dispersed on a carbonaceous powder
- 20 substrate. This assembly of electrodes and membrane is often referred to as the membrane electrode assembly (MEA).

- Hydrogen fuel is supplied to one electrode (the anode) where it is oxidised to release electrons to the anode and hydrogen ions to the electrolyte. Oxidant (typically air or oxygen) is supplied to the other electrode (the cathode) where electrons from the cathode combine with the oxygen
- 25 and the hydrogen ions to produce water. A sub-class of proton exchange membrane fuel cell is the direct methanol fuel cell in which methanol is supplied as the fuel. This invention is intended to cover such fuel cells and indeed any other fuel cell.

In commercial PEM fuel cells many such membranes are stacked together separated by flow field plates (also referred to as bipolar plates or separators). The flow field plates are typically formed of metal or graphite to permit good transfer of electrons between the anode of one membrane and the cathode of the adjacent membrane. The flow field plates have a pattern of grooves on their surface to supply fluid (fuel or oxidant) and to remove water produced as a reaction product of the fuel cell.

Various methods of producing the grooves have been described, for example it has been proposed to form such grooves by machining, embossing or moulding (WO00/41260), and (as is particularly useful for the present invention) by sandblasting through a resist (WO01/04982).

International Patent Application No. WO01/04982 disclosed a method of machining flow field plates by means of applying a resist or mask to a plate and then using sandblasting (or other etching method using the momentum of moving particles to abrade the surface, e.g. waterjet machining), to form features corresponding to a pattern formed in the mask or resist.

Such a process was shown by WO01/04982 as capable of forming either holes through the flow field plates, or closed bottom pits or channels in the flow field plates. The process of WO01/04982 is incorporated herein in its entirety, as giving sufficient background to enable the invention.

In practice, the majority of plates made to date have been formed by milling the channels.

WO00/41260 discloses a flow field geometry in which substantially straight parallel channels are provided of a width less than about 0.75mm.

WO00/26981 discloses a similar geometry in which highly parallel flow channels of a width less than 800µm separated by lands of less than 800µm are used and in which the inter-channel land area is less than 25% of the flow field. Preferred land widths are narrower still. This geometry is stated to improve gas distribution as reducing the need for lateral gas dispersion through the MEA (referred to in WO00/26981 as the DCC [diffusion current collectors]). The geometry is also stated to reduce electrical resistance as it reduces the electrical path length to land areas.

There is a conflict between electrical and gas properties described in WO00/26981, in that reduced land areas are stated to increase electrical resistance. WO00/26981 states that these conflicting requirements may be optimised. WO00/26981 states that the pattern of highly parallel micro-channels may contain interconnections or branch points such as in hatchings or grid patterns. One advantage of the use of narrow channels is stated to be that this encourages water droplet formation across the channels so permitting efficient water removal. However this advantage may not be seen where a grid pattern is used as the pressure either side of a water droplet is likely to be substantially equal.

Cited against WO00/26981 are:-

- 10 • US 3814631, which discloses an electrode construction in which micro-channels of more than 0.3mm wide are provided in a frame edge leading to a textured electrode in which protrusions on one face of the electrode match depressions in the opposed face of the electrode.
- 15 • US 5108849, which discloses a plate having serpentine tracks of 0.76mm (0.03 inch) width or more with land widths of 0.254mm (0.01 inch) or more.
- WO94/11912, which discloses a plate having discontinuous tracks of 0.76mm (0.03 inch) width and depth. These tracks may be interdigitated.
- WO98/52242, which discloses means for humidifying the membrane,

20 Narrow channels are known for other devices, for example, WO94/21372 discloses a chemical processing apparatus comprising a three dimensional tortuous channel formed by aligning part channels in adjacent discs. Such a construction has not been used for a fuel cell.

None of the fuel cell related patents disclose a structure of relatively coarse gas delivery channels leading to fine gas channels.

~~To ensure that the fluids are dispersed evenly to their respective electrode surfaces a so-called~~

gas diffusion layer (GDL) is placed between the electrode and the flow field plate. The gas diffusion layer is a porous material and typically comprises a carbon paper or cloth, often having a bonded layer of carbon powder on one face and coated with a hydrophobic material to promote water rejection. It has been proposed to provide an interdigitated flow field below a macroporous material (US-A-5641586) having connected porosity of pore size range 20-100 μ m allowing a reduction in size of the gas diffusion layer. Such an arrangement permits gas flow around blocked pores, which is disadvantageous. Build up of reactant products (such as water) can occur in these pores reducing gas transport efficiency. Additionally, such a structure increases the thickness of the flow field plate.

The applicant has analysed what happens in a fuel cell and have come to the conclusion that the gas diffusion layer does not do what it's name implies. The theory had been that the gas diffusion layer serves to permit gas to diffuse across the whole surface of the membrane so that large portions of the membrane are active in the cell reaction. The applicant has found that, in simple models, the gas appears not to access the whole of the lands between the channels, but only the area above the channels and a small margin surrounding the channels, the majority of the electricity generation taking place in this restricted region.

This is supported by the observation that interdigitated channels show higher electrical efficiencies since the gas is forced into the areas above the lands. The gas diffusion layer does however actually serve a useful purpose in carrying current from those areas of the membrane electrode above the channels to the lands, and in providing mechanical support to the membrane electrode to prevent it being squeezed into the channels. It has been proposed by some to stiffen the membrane electrode.

The gas diffusion layer in carrying current from those areas where electricity is generated to the lands, does of course result in electrical losses due to the electrical resistance of the gas diffusion layer. Present day gas diffusion layers are chosen as a delicate balance between the needs of mechanical strength, electrical conductivity, and gas permeability.

~~A combined flow field plate and gas diffusion layer has been described in US-A-6037073 and~~
comprises a selectively impregnated body of porous carbon material, the impregnation
hermetically sealing part of the plate. Such an arrangement has the drawbacks that it is
complicated to make reproducibly and that it permits gas flow around blockages as in
5 US-A-5641586.

An assembled body of flow field plates and membranes with associated fuel and oxidant supply
manifolds is often referred to a fuel cell stack.

Although the technology described above has proved useful in prototype and in some limited
commercial applications, to achieve wider commercial acceptance there is now a demand to
10 reduce the physical size of a fuel cell stack and to reduce its cost. Accordingly, a reduction in
the number of components could have beneficial results on size and cost (both through material
and assembly costs).

Also, the prior art flow field plates have provided flow fields of matrix, serpentine, linear, or
interdigitated form but have not looked to other physical systems for improving the gas flow
15 pathways. Matrix flow fields (in which a grid of lands is provided to support the gas diffusion
layer and gas flows between the lands) theoretically provide good gas flow but in practice have
the disadvantage that water is readily trapped within the matrix and blocks it. Further, any
blockage can lead to stagnant areas in the flow field.

Linear and serpentine flow fields have fewer problems with water blockage or stagnant areas
20 but have a lower gas flow for a given pressure drop across the flow field. Serpentine flow field
patterns also tend to have a problem with gas "short circuiting" by passing from one channel to
an adjacent channel having a significantly lower pressure.

Interdigitated flow fields provide a highly efficient delivery of gas but have the disadvantage
that high pressures are required to force the gas from the incoming flow field, through the gas
25 diffusion layer, to the outgoing flow field and this results in high parasitic losses.

Additionally, the applicant has modelled the behaviour of conventional flow field plate designs
and found that under conditions of high demand (e.g. currents of $0.6\text{A}/\text{cm}^2$ or higher) such
conventional plates are liable to depletion of oxidant and/or fuel over large parts of the flow
field plate.

Known requirements of gas flow fields are:

- sufficient land area to support the GDL and maintain a cavity for flow of gas
- sufficiently narrow channels to prevent the GDL squeezing into and blocking the channels under the compressive pressures holding the stack together
- 5 • and, from WO00/26981, sufficiently narrow channels to reduce the path length of current from areas over the channel to lands, and sufficiently narrow lands to reduce the diffusion distance of gas to areas over the lands.

What WO00/26981 does not solve, except by partition of flow field plates into separate areas, is that narrow channels imply a high pressure drop and so a distinct difference in gas availability
10 from one end of the channels to the other.

In a conventional flow field plate design, the pressure at one end (the inlet end) of the flow field is significantly lower than at the other end (the outlet end) as reactant gases are both consumed in operation of the fuel cell and because of the resistance to flow of the gases. As the demand for fuel or oxidant increases, the ability of such arrangements to deliver reactant gas effectively
15 towards the reactant gas outlet diminishes. The applicant has realised that what is required is a means to provide efficient gas delivery to the whole of the working surface of the fuel cell, and in particular in the region of the flow field outlet, so that starvation of reactants does not occur.

The applicant has realised that by looking to physiological systems (the lung) improved flow field geometries may be realised that are likely to have lower parasitic losses due to their
20 shorter gas flow pathways. In the geometries contemplated, gas is delivered by gas delivery channels to a permeable wall, and is then transferred through the permeable wall to gas removal channels.

The applicant has also realised that such geometries are less likely to suffer from gas short-circuiting, since such an arrangement permits high flow rates at low pressure drops. Such
25 geometries also promise more even distribution of reactants over the flow field.

Accordingly, the present invention provides a flow field plate for a fuel cell or electrolyser, comprising one or more gas delivery channels, one or more gas removal channels, and a permeable wall separating same.

The permeable wall may comprise a plurality of gas diffusion channels and may be of impermeable material.

The permeable wall may be of convoluted form.

5 The permeable wall may have a length of 10 or more times the maximum width of the flow field.

Further features of the invention are set out in the claims and as exemplified by the following description with reference to the drawings in which:-

Fig. 1 shows in plan a flow field plate design in accordance with the invention;

Fig. 2 shows an enlarged plan view of area A of Fig. 1;

10 Fig. 3 shows the results of modelling a five track serpentine flow field;

Fig. 4 shows the results of modelling a flow field in accordance with the present invention and the design of Figs. 1 & 2; and

Fig. 5 shows the results of using an abrasive blasting technique

Fig. 6 show an alternative a flow field plate design in accordance with the invention

15 Fig. 7 shows an enlarged plan view of area E of Fig. 1.

Figs. 1 and 2 show a flow field plate in accordance with the invention. A flow field plate 1 comprises manifolds and fastening holes 2 in a peripheral frame 18 that forms no part of the actual flow field. The plate also comprises a gas supply channel 3 to which a reactant gas is delivered by a manifold (not shown). Channel 3 communicates with gas delivery channels 4.

20 Gas delivery channels 4 themselves connect to gas delivery sub-channels 5. In similar manner, a gas drain channel 6 connects with gas removal channels 7 and gas removal sub-channels 8.

The gas delivery channels and sub channels 4,5 and the gas removal channels and sub channels 7,8 define between them a wall 9 having a plurality of diffusion channels 10 that offer a flow path from the gas delivery channels and sub channels 4,5 to the gas removal channels and sub-channels 7,8. In a typical case, for a small fuel cell having a plate size of $\sim 10\text{cm} \times 10\text{cm}$ and a flow field working area of $\sim 6.5\text{cm} \times 6.5\text{cm}$, the width of the gas delivery channels would be about 1.25mm, for the sub-channels about 0.5mm, and for the diffusion channels about 0.125mm.

The wall is convoluted on two scales.

On a first scale, it extends in a pleated or concertinaed manner from the gas supply channel 3 to the gas drain channel 6 and comprises wall segments 16 along each fold of the wall, and end wall segments 17 at each turn of the wall. The length of each fold of the wall is about 6cm in the example shown.

On a second scale, the walls between end wall segments 17 are themselves pleated or concertinaed to form the gas delivery and gas removal sub channels 5,8. The length of the gas delivery and gas removal sub-channels is about 2.5mm in the example shown.

This pattern can be repeated on a smaller or larger scale still.

This fractal type arrangement of the flow field, in which gas passes through progressively diminishing channels, means that the arrangement is to some extent scalable to the size of the flow field plate. It further ensures a large surface area to the permeable wall.

This arrangement also ensures that the GDL is well supported by the flow field while ensuring that parts of the MEA lying above the land areas of the flow field are only a short distance from a channel (typically, for the arrangement shown, for the wall segments 16, within 0.5 mm or less of the closest channel and for end wall segment 17, within 1.25mm or less). This arrangement is readily scalable such that smaller wall segments 16 may be used giving still better access of gas to the area above the lands. Preferably no part of the flow field (and in particular of the wall segment 16) is more than 0.25mm from the closest gas delivery or diffusion channel.

~~The flow field can be considered as a series of low flow resistance gas delivery channels (4,5)~~ connected to a series of low flow resistance gas removal channels (7,8) by a permeable membrane 9 which may be formed by a series of high flow resistance channels 10 in an impermeable wall.

- 5 The flow field may also be considered as a series of gas delivery channels (4,5) delivering gas to regions distributed across the face of the flow field, a series of gas removal channels (7,8) removing gas from regions distributed across the face of the flow field, and a permeable wall controlling the rate of transfer of gas from said gas delivery channels (4,5) to said gas removal channels (7,8).
- 10 The corners of the flow field segments are preferably rounded so as to reduce the points for nucleation and/or adherence of water droplets.

In the flow field shown, the length of the wall 9 is considerably longer than the maximum width of the flow field (the diagonal B-B) being at least 10 times greater.

- The applicant has modelled a test plate of the above dimensions with a plate having the same flow field working area and having the same proportion of land area to channels but having a five channel serpentine configuration. The modelling indicated that for a given flow rate the serpentine channel flow field had a pressure drop of 200Pa whereas the plate according to the invention had a pressure drop of 53Pa. While both pressure drops are small, in a large system such a difference in pressure drop could have an appreciable effect on parasitic losses, reducing the energy requirement for the inventive design in comparison with the serpentine design.
- 15
- 20

Additionally, at high currents, the serpentine arrangement showed a significant diminution in gas flow towards the outlet as shown by Fig. 3 in which the darker areas show that the majority of the plate is starved of reactants. In contrast, under the same conditions, the inventive arrangement showed less of a loss in gas flow and so is able to sustain current generation over more of the plate.

25

To reduce such loss as was present, the applicant provides wider diffusion channels toward the outlet ends of the plate (region C) than near the inlet ends of the plate (region D) and indeed the channel widths and/or depths can be varied along the length of the permeable wall as required to provide a uniform flow across the plate.

Alternatively, or additionally, the number of gas diffusion channels per unit length can vary along the length of the permeable wall, so as to provide more channels in regions that would otherwise be depleted in gas were constant numbers of channels per unit length used.

5 Additionally, some or all of the gas diffusion channels may be convoluted to provide a tortuous path and so higher resistance to gas flow. The proportion of convoluted channels and/or their degree of convolution may be varied along the length of the permeable wall as required.

10 To form both gas delivery and gas diffusion channels a technique such as sand blasting may be used in which a patterned template or resist is placed against the surface of a plate, the template or resist having a pattern corresponding to the desired channel geometry. Such a technique is described in WO01/04982, which is incorporated herein in its entirety as enabling the present invention. With this technique the plates may be formed from a graphite/resin composite or other non-porous electrically conductive material that does not react significantly with the reactants used.

15 It is found with this technique that the profiles of channels of different width vary due to the shadow cast by the mask. Fig. 5 shows a flow field plate 11 having a narrow channel 12 formed in its surface. Because of the shadowing effect of the resist used in forming the channel the channel is exposed to sandblast grit coming effectively only from directly above. This leads to a generally semicircular profile to the channel and to a shallow cutting of the channel.

20 For progressively larger channels (13 and 14) the resist casts less of a shadow allowing sandblasting grit from a progressively wider range of angles to strike the surface of the flow field plate, so allowing both deeper cutting of the surface and a progressively flatter bottom to the channel.

25 Accordingly, by applying a resist with different width channels to a plate and exposing the plate and resist to sandblasting with a fine grit, a pattern of channels of different widths and depths can be applied.

This is advantageous in the present context, as the channels in the wall do not need to be of the same depth as the gas delivery channels, and indeed are functioning as a choke to restrict gas flow through the wall.

Alternatively, the wall could be deposited onto a plate (e.g. by screen printing or the like) and in this case could be formed of a gas permeable material without the use of gas diffusion channels. It will be readily apparent to the person skilled in the art that there are many ways of producing a permeable wall.

- 5 While the wall 9 shown is defined by gas channels and sub-channels, it is readily apparent that more or less convoluted walls can be used.

Figs. 6 and 7 show an alternative flow field plate design in accordance with the principles of the present invention. A flow field plate comprises a central area 19 (for use with a surrounding frame 18 [not shown] as in Fig. 1). This has a gas supply channel 3 and a gas drain channel 6 and end wall segments 17 as in Fig. 1. The permeable walls are defined by an array of lands 20 forming a network of fine gas diffusion channels therebetween. Although circular lands are shown, the applicant has found that hexagonal or other lands offering a relatively constant channel width therebetween are preferred.

The present invention thereby presents a flow field that promises:-

- 15
- higher gas flow for a given pressure drop than a linear or serpentine flow field of the same land area;
 - comparable gas flow to a matrix flow field while providing a sufficient pressure drop to clear water
 - comparable performance to an interdigitated flow field without the high parasitic losses
- 20 normally associated with same.

CLAIMS

1. A flow field plate (separator) for a fuel cell or electrolyser comprising on at least one face an assembly of channels comprising one or more gas delivery channels, one or more gas removal channels, and a permeable wall separating same.
- 5 2. A flow field plate as claimed in Claim 1, in which the permeable wall comprises a plurality of gas diffusion channels.
3. A flow field plate as claimed in Claim 2, in which no part of the permeable wall is more than 1.25mm from a gas diffusion channel.
- 10 4. A flow field plate as claimed in either of Claims 2 or 3, in which the permeable wall comprises impermeable material.
5. A flow field plate as claimed in any one of Claims 1 to 4, in which the permeable wall is of convoluted form.
- 15 6. A flow field plate as claimed in Claim 5, in which the permeable wall is concertinaed, having wall segments extending along each fold of the wall, and end wall segments at each turn of the wall.
7. A flow field plate as claimed in either of Claim 5 or 6, in which the permeable wall is convoluted on two or more scales.
- 20 8. A flow field plate as claimed in Claim 6 or 7, in which the maximum distance from any part of the land area of the flow field to the nearest gas delivery or gas diffusion channel is less than 1.25mm.
9. A flow field plate as claimed in any one of Claims 6 to 8, in which the maximum distance from any part of the land area of wall segments extending along each fold of the wall to the nearest gas delivery or gas diffusion channel is less than 0.5mm.
- 25 10. A flow field plate as claimed in any one of Claims 1 to 9, in which the maximum distance from any part of the land area of the flow field to the nearest gas delivery or gas diffusion channel is less than 0.25mm

11. A flow field plate as claimed in any one of Claims 1 to 10, in which the permeable wall has a length of 10 or more times the maximum width of the flow field.
12. A flow field plate as claimed in any one of Claims 1 to 11, in which the corners of the flow field segments are rounded.
- 5 13. A flow field plate as claimed in any one of Claims 1 to 12, in which the permeability of the permeable wall varies along its length so as to provide a more even distribution of gas than using a constant permeability permeable wall.
- 10 14. A flow field plate as claimed in Claim 13, in which the permeable wall comprises gas diffusion channels and the width and/or depth of these channels varies along the length of the permeable wall.
- 15 15. A flow field plate as claimed in either Claim 13 or 14, in which the permeable wall comprises gas diffusion channels, and the number of gas diffusion channels per unit length varies along the length of the permeable wall.
16. A flow field plate as claimed in any one of Claims 13 to 15, in which the permeable wall comprises gas diffusion channels, and some or all of the gas diffusion channels are convoluted to provide a tortuous path.
17. A flow field plate as claimed in Claim 16, in which the proportion of the convoluted gas diffusion channels is varied along the length of the permeable wall.
- 20 18. A flow field plate as claimed in either Claim 16 or 17, in which the degree of convolution the convoluted gas diffusion channels is varied along the length of the permeable wall.
19. A flow field plate, as claimed in any preceding claim, in which the permeable walls is defined by an array of lands forming a network of fine gas diffusion channels therebetween.
- 25 20. A method of making a flow field plates as claimed in any one of Claims 1 to 19, by applying a patterned resist having different width channels to a plate and exposing the plate and resist to sandblasting with a fine grit, to produce a pattern of channels of different widths and depths in the flow field plate.

ABSTRACT

A flow field plate for a fuel cell or electrolyser comprises on at least one face an assembly of channels comprising one or more gas delivery channels, one or more gas removal channels, and a permeable wall separating same. The permeable wall may comprise a plurality of gas
5 diffusion channels.




Fig.2.




Fig.3.




Fig.4.





Fig. 5.







Fig.6.

Fig.7.



**This Page is Inserted by IFW Indexing and Scanning
Operations and is not part of the Official Record**

BEST AVAILABLE IMAGES

Defective images within this document are accurate representations of the original documents submitted by the applicant.

Defects in the images include but are not limited to the items checked:

☒ **BLACK BORDERS**

☐ **IMAGE CUT OFF AT TOP, BOTTOM OR SIDES**

☐ **FADED TEXT OR DRAWING**

☐ **BLURRED OR ILLEGIBLE TEXT OR DRAWING**

☐ **SKEWED/SLANTED IMAGES**

☐ **COLOR OR BLACK AND WHITE PHOTOGRAPHS**

☐ **GRAY SCALE DOCUMENTS**

☒ **LINES OR MARKS ON ORIGINAL DOCUMENT**

☐ **REFERENCE(S) OR EXHIBIT(S) SUBMITTED ARE POOR QUALITY**

☐ **OTHER:** _____

IMAGES ARE BEST AVAILABLE COPY.

As rescanning these documents will not correct the image problems checked, please do not report these problems to the IFW Image Problem Mailbox.